


# Remote Handling Operations at SNS

Mike Dayton

Remote Handling Engineer




# Remote Handling

- **Since SNS operation began in 2006, a significant amount of remote handling operations have occurred**
- **Remote handling at SNS encompasses:**
  - **Major component replacement (target, PBW, CVI, etc)**
  - **PIE operations**
    - **Target Post-Irradiation Examination relies heavily on remote handling**
  - **Waste shipment operations**
    - **Cask loading and waste handling require significant remote handling**
- **The following provides an overview of these remote handling operations along with plans for future operations**

# Remote Handling

- Major Remote Handling Component Replacements

Power on Target



# Remote Handling Planning

- **Planning for remote handling operations utilizes the following variables:**
  - **End of life tracking for major components**
    - A spreadsheet is maintained to track end of life for targets, PBWs, Inner Reflector Plug, Ring Injection Dump window and beam stop, etc
    - End of life for each item is estimated based on projected beam power, run schedules, availability, etc., and then updated monthly with actuals
  - **Beam Line Instrument requirements**
    - Shutter replacements and CVI installation requirements are tracked based on instrument operational need dates
- **These variables are then managed to ensure tooling and resource availability and to provide near and long term maintenance planning**

# Target Module Replacement

- **Target Replacement**

- **Target Maintenance Environment**

- Target Service Bay
- Maintenance Equipment
- Radiation and Contamination

- **Target Replacement Operations**

- **Target Replacement Lessons Learned**



SNS Target Module

- **Replacement of the target modules is accomplished using only remote handling tooling and procedures (hands-on operations are not possible)**

- **While the tooling and procedures utilized enable successful replacement of the targets, continuous process improvement is employed to ensure successful replacements**

# Target Module Replacement

- Four window workstations each containing a pair of master-slave manipulators are built-into the target Service Bay. Only one workstation is dedicated to target change-out
- A servo-manipulator is required to perform most operations including bolt torquing, tool transport, inspections and precision operations



**Manipulator Gallery**



**Remote Handling Control Room**

# Target Module Replacement

- **Radiation and Contamination Environment:**
  - Experience has shown that the isotopic particulate contamination is long-lived and wide-spread inside the Service Bay
    - A systematic program of obtaining smears from within the Service Bay has been initiated to characterize the contamination environment
      - Current contaminations levels range from 10,000 dpm to 3-5,000,000 dpm
  - Radiation levels at various locations in the process bay are tracked during target replacements
    - The maximum dose rates observed during Target #3 replacement:
      - Mercury Pump: 21.45 R/hr (.215 Gy/hr)
      - Coolant Water Return Line from Carriage: 2475 R/hr (24.75 Gy/hr)
      - Mercury Return Line from Carriage: 2717 R/hr (27.17 Gy/hr)


# Target Module Replacement

- **Following each target replacement, a “lessons learned” activity is conducted to ensure continuous improvement of the replacement procedures and tooling**
  - Enhancements to the process and tooling improvements enable replacement of a target in approximately 100 hours
- **Each target replacement yields new challenges and issues**
  - **Target #1: Leaking Hiltap fitting in the mercury process loop required extensive real-time testing to identify and correct**
  - **Target #2: Inadequate target bolt torquing resulted in degraded mercury seal testing results requiring additional effort to identify and correct the issue prior to target insertion**
  - **Target #3: Leaking Hiltap fitting in the water coolant loop required real-time testing to identify and correct resulting in a two day delay in completion of target replacement**



# Proton Beam Window Replacement


- Two Proton Beam Window modules have been replaced at SNS:
  - The initially-installed window had received just over 3000 MW-hrs of accumulated energy resulting in an approximate dpa level of 6.5
  - The second window had received ~ 5200 MW-hrs of energy resulting in a dpa level of approximately 10.5
  - The Proton Beam Windows incorporate the optics portion of the Target Imaging System enabling the viewing of the coated Target Module along with halo thermocouples to aid in beam centering
  - Following both installations, Core Vessel and RTBT flight tube vacuum leak testing has indicated excellent PBW inflatable seal function



# Proton Beam Window Replacement

- Replacement of a PBW module involves the following basic operations:
  - Removal of five shield blocks (45 tons of shielding)
  - Drying (water removal) of PBW module
  - Cutting and removal of activated utility piping
  - Withdrawal of PBW module from cavity
  - Installation of new PBW module
  - Connection of utility piping
  - Leak testing of inflatable seals and piping connections
  - Re-installation of shielding

***PBW replacement requires approximately 9 days***



# Proton Beam Window Replacement



**New PBW Installation**

**Jumper  
Installation**



**TIS Fiber  
Optic Cable  
Installation**

# Proton Beam Window Replacement

- Radiological surveys are done during every aspect of PBW replacement operations. The following are some of the findings from the most recent operation:


Item	Dose Rates (1)	Contamination	
PBW Top Block	Negligible	None	
Shield Block 6	Negligible	Minor Be-7 on lower surface	
Shield Block 5	.1 - .2 mR/hr	Minor Be-7 contamination	
Shield Block 4	1.5 mR/hr	Minor Be-7 contamination	
Shield Block 3	680 mR/hr	150,000 dpm	
Utility Piping	~ 120 mR/hr	None (4)	
PBW Module	600 R/hr (2)	(3)	
Notes:			
1. Contact dose rates unless otherwise specified.			
2. Dose rate at approximately 1 m - unshielded.			
3. No measurement taken.			
4. No external contamination.			

# Shutter and CVI Replacement

- **At the completion of SNS construction, seven instrument beam lines contained concrete shutter plugs in lieu of fully-functional shutters**
  - To date, four of these beam lines have been updated to remove the shutter plug assemblies and install operational shutters
- **Additionally, four beam lines contained Core Vessel Insert plugs in lieu of functional inserts**
  - The BL 16 CVI was replaced during the winter 2011 outage
- **The following slides give an overview of the BL 16 CVI and shutter replacement operation**


# Shutter and CVI Replacement

Target Monolith



# Shutter and CVI Replacement

- Each beam line has its own user-operated primary shutter
  - 12 single channel shutters
    - 30 tons each (27,215 kg)
  - 6 multi channel shutters
    - 50 tons each (45,350 kg)
  - Each shutter incorporates a beam stop and a helium-purged optical insert



**Multi Channel  
Shutter Assembly**

**195" x 78" x 31"  
(4.9m x .8m x 2m)**

ISOMETRIC VIEW  
WEIGHT: 49.16 TONS

# Shutter and CVI Replacement

BL 16 CVI

- ~ 1900 lbs (860 kg)
- 22 feet tall (6.7 m)

- The CVI interfaces directly with the Core Vessel and becomes part of the Vessel vacuum boundary
  - Aligns to the Core Vessel via two alignment pins
  - Secured using four 1.25” (31.75mm) diameter studs
  - Utilizes a double o-ring (metal) seal
    - These seals require 40,000 lbs (~18,100 kg) of tensile force in each stud
    - Tensioning methods are used to stretch the studs in lieu of torquing
      - Metal seals require high compressive forces
      - Tensioning provides more repeatable, consistent seal compression
- Comprises the innermost portion of the instrument beam line
- Each CVI is water cooled and purged with helium





# Shutter and CVI Replacement

- Installation of the new BL 16 CVI proceeded following loading of the CVI into the Robot and installation of the O-ring seal:



**Loading of BL 16  
CVI into Robot**



Utility Tubing

Chamfered Clearance Holes  
For Core Vessel Studs

O-Ring Seal

# Shutter and CVI Replacement

- Stud tensioning was completed followed by leak testing of the CVI O-ring seal
  - Leak testing involves evacuation of the interstitial region between the two o-rings followed by isolation and then a rate-of-rise test

## Testing:

Test criteria: Evacuate to  $< 100\text{mTorr}$   
Isolate and measure rate-of-rise over  
3-hour period

Permissible pressure rise:  $50\text{ mTorr}/3\text{ hr}$

Test results:  $83\text{ mTorr}/3\text{ hr}$

Originally installed (hands-on) CVI plug was only able to achieve a  $95\text{ mTorr}/3\text{ hr}$  rate, so new CVI performed better than the initially-installed plug

Subsequent Core Vessel testing indicated an excellent leak rate of  $.017\text{ Torr-L}/\text{sec}$



**Seal Leak Testing**

# Shutter and CVI Replacement


- The replacement process concluded with the installation of the new BL 16 shutter components:



**Lower Segment  
Installation  
(31,000 lbs/14,000kg)**



**Middle Segment  
Installation  
(20,000 lbs/9100kg)**



**Upper Segment  
Installation  
(50,000 lbs/22,600kg)**

# Shutter and CVI Replacement

- **This operation was the first fully-remote replacement of a CVI at SNS**
- **The replacement was completed over a period of 15 working days**
  - **Total cumulative dose for all workers involved in the replacement was 7 mR (.07 mSv)**
  - **Maximum dose for any individual was < 2 mR (.02 mSv)**
- **While several challenges were encountered, the design of the tooling, extensive testing and innovative real-time solutions enabled a successful replacement of this critical component**

# PIE Operations

- **Post-Irradiation Examination (PIE) has been conducted on each of spent target modules following replacement**
- **PIE operations have utilized the following tools:**
  - **Pressure decay testing to verify the integrity of portions of the target vessel (interstitial volume and water shroud)**
  - **Nose Sampling to remove samples of each target nose for subsequent testing**
  - **Video scope inspection to enable visual inspection of areas of interest within the mercury vessel**
- **Non-destructive methods (decay testing and video scope) are employed prior to nose sampling**

# PIE Operations

- Target Video Scope Image:



Video scope image of the interior of the Target Mercury Vessel at the Nose location showing significant cavitation damage



Video scope being inserted into target nose following sample cutting

# PIE Operations

- Target Nose Sampling Operations:



Spent Target suspended vertically in remote-operated Nose Sampling Cutter Assembly



View of Target nose following the fourth cutting operation

# Waste Shipment Operations

- **SNS is design to utilize an over-the-road waste shipment cask known as the TN-RAM for disposal operations**
  - **To date, three waste shipments have been completed:**
    - Target #1 shipped in May 2010
    - PBW #1 shipped in December 2010
    - Target #2 shipped in May 2011
  - **Cask loading occurs via the Service Bay and involves significant remote handling**
    - Handling of activated components
    - Loading of the cask liner
    - Cask liner bolt torquing



# Waste Shipment Operations

## PBW Waste Preparation



**PBW Cask Liner is Loaded into the Service Bay**



**PBW Cask is positioned over Top Loading Port**



**PBW is lowered into Service Bay for loading Into Liner**

# Waste Shipment Operations



**Cask Lifting from Truck**



**Translating Cask over for Lowering into Cask Cart**

# Waste Shipment Operations

- Following loading of the Cask, leak testing and radiological surveys are performed to ensure DOT compliance




# Future Remote Handling Operations

- **Ring Injection Dump (RID) Component Replacement**
  - **The RID contains two items that must be replaced via remote handling operations:**
    - **A window to isolate the high vacuum of the accelerator from the nominal atmospheric pressure of the RID cavity**
    - **A beam dump fabricated from copper plates to absorb the energy from the proton beam**
  - **Current life expectancy planning for these items indicate that replacement will be required no sooner than the summer outage of 2016**
  - **Procurement of the tooling required to replace these items is underway (AIP-29)**
  - **Procurement of a spare Beam Stop Assembly is also in work (AIP-29)**

# Future Remote Handling Operations

- Ring Injection Dump (RID) Component Replacement



# Future Remote Handling Operations

- **Inner Reflector Plug (IRP) Replacement**
  - **The SNS IRP has a nominal life expectancy of 30,000 MW-hrs**
    - **Based on current planning, the first IRP replacement will occur no sooner than the winter outage of 2015**
  - **The remote handling tooling has been fabricated and delivered**
  - **Mockup testing and detailed procedure development remains to be completed**

# Future Remote Handling Operations

- **Replacement of the IRP is complex for many reasons**
  - **Target module retraction is required due to the fact that the target nose extends into the Lower Inner Plug**
    - **Target retraction itself requires 2-3 days of remote operations in the Service Bay**
  - **The IRP is vertically integrated into the Core Vessel through the Shutter Drive Equipment Room(SDER) requiring the unstacking of a significant amount of shielding**
    - **46 shield blocks + Monolith Shine Shield Beams must be removed to access the IRP**
  - **The size and weigh of the IRP requires removal in segments**
  - **The large amount of utility piping complicates removal**
    - **This piping must be accessed, cut and removed during the operation**

# Future Remote Handling Operations

## SDER Showing Access to IRP

Shield Plate  
Directly Above  
IRP

Monolith Shine Shield Beams

Pan Shield  
Blocks

Hydraulic  
Shutter  
Drives



PBW Cavity



# Future Remote Handling Operations


## Removal of the Lower Inner Plug

Lead-Shielded Cask  
Positioned over  
IRP Cavity

Weight of Cask + IRP  
Segment approaches the  
capacity of the 50T crane

Air-operated Chain  
Hoist with Remote  
Grapple Fixture

Lower Inner Plug  
Is withdrawn into Cask



Lead shield door provides  
technician protection during  
removal of Cask

# Future Remote Handling Operations

- **Near term:**
  - Target #4 replacement: January 2012
  - PBW #3 replacement: July 2012
  - Target #5 and BL 9 Shutter/CVI: January 2013
- **Inner Reflector Plug Replacement**
  - Anticipated to occur no sooner than January 2015
  - All tooling has been designed and delivered
  - Testing and procedure development remain
- **Ring Injection Dump Window and Beam Stop**
  - Anticipated to occur no sooner than January 2016
  - Tooling procurement in work