


SRF Activities

Presented at the
Accelerator Advisory Committee
Review

John Mammosser
SCL Systems Group
Research Accelerator Division

March 24-26, 2015



Superconducting RF Activities at SNS

- **SRF activities at SNS are focused in three primary areas**
 1. Support of Superconducting Linac (SCL) operations, maintenance and improving operational performance
 2. Support of SRF and Plasma Processing R&D aimed at improving installed operational gradients
 3. Operating and improving SRF facilities to carryout the above activities

SCL Support Activities - Since last Review

- **Highlights of support activities for reliable LINAC operation:**

- Removal of one Medium Beta (MB) and one High Beta (HB) cryomodule for replacement of a RF coupler in each module
 - Standard servicing of these cryomodules was conducted
 - Tested in test cave to verify performance
 - Installation of these two cryomodules back into service
 - **No MB spare is still a concern**
- Removal of a low performing HB cryomodule (now the spare HB), this CM will be serviced and part of Plasma R&D development efforts in the next few months
- Warmup of three cryomodules for warm section repair



SCL Current Support Activities

- **Typical Cryomodule Servicing**
 - Removal of HOM probes and piezo fast tuners
 - Repair of CM components (reliefs, diodes, tuners, etc.)
- **In-situ thermal cycling of CM's to recover performance**
- **Quality Assurance Team Activities**
 - Focus on development of repeatable repair procedures and capturing of critical data
 - Reducing particulate contamination during repairs and R&D activities
 - Particulate contamination leads to reduced gradients due to field emission effects


Quality Assurance Team Activities

- Reducing particulate generation and migration is a priority
- Topical areas visited by the QA team
 - Particulate control during venting and purging (example next)
 - Particulate control during cryomodule beam line component removal and replacement
 - Cleaning step effectiveness and improvements (just started)


Example of QA Activities



Normal Pumpdown




580 particle counts




Normal Pumpdown

Time = 10 min




Name	Bin1	Bin2	Bin3	Bin4	Bin5
	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>

Bypass Pumpdown



1 particle counts



Bypass Pumpdown

Time = 19 min



Name	Bin1	Bin2	Bin3	Bin4	Bin5
	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>




Development of in-house MB spare

- **There is a strong need for a spare MB Cryomodule!!**
 - In-house cavity prototyping effort is underway with MB cavity, procedures developed and tooling verified
 - Developing local vendor capabilities
 - **Shorten long lead procurements activity (Response to AAC2012 recommendation)**
 - Next step is to verify trimming procedure and then fabricate first MB cavity spare in niobium
 - The spare MB CM effort is awaiting funding



Horizontal Test Apparatus Developed, Integrated and Commissioned

- Qualifies Cavity in a Similar Way to Accelerator Operations
- HPRF and Diagnostics
 - Using 5MW klystron in the RFTF
 - 8 radiation detectors, camera system for imaging inside of cavity, 20 temperature sensors, etc
- Horizontal Testing
 - Used first to support plasma processing R&D with HB cavities fully dressed



SRF Support of plasma processing R&D

- Preparation for HTA test
 - High beta cavities dressed with helium vessel
 - Preparation of cavities in clean room
 - Installation of cavity in HTA
 - Integration of HTA in the SNS test cave
 - Support activities during test






Vertical Test Area

- Commissioned at 4.2K 9/2013
- Started commissioning at 2K with Kinney skid 1/2015
- Current focus is on qualifying the two HB cavities with modified end-groups
 - Cavities had end groups changed to remove HOM cans and improve thermal stability
 - Verify vertical performance at 2K



CTF System Installed and Commissioned



CTF Refrigeration System Specifications

Description	Specification
Refrigeration	650W @ 4.4K
Liquefaction	240 L/hr
He High Header Pressure	13 atm
Helium Mass Flow	81 g/s
Oil Content	< 0.1 ppmv
He Low Header Pressure	1.05 atm
Start Up Time	< 6 hours

CTF Liquid Helium Fill Station

- **The CTF Fill Station now commissioned and ready for use**
 - Needed to mitigate supply chain issues during helium shortages
 - Allows for responding to emergency needs of liquid helium supply
 - Supports sample environment and instrument operations
- **The CTF Fill Station is also integrated with the VTA**
 - Supplies liquid helium to VTA
 - Potentially allows operation of the VTA without running the CTF
 - Liquid helium can be transferred from the VTA back to the Fill Station
 - Power is conserved with this feature

Additional SRF Facilities

– Cavity Inspection Station

- Internal cavity inspection system construction complete, currently developing tooling and capture hardware

– Centrifugal Barrel Polishing

- Installed but not commissioned, procedure be developed for a cavity repair

– Niobium Heat Treatment Furnace

- Furnace installed, commissioned and R&D activities started

– Cleanroom assembly facilities continued operations and improvements

- Degreasing of cavity and new component cleaning station (on site but not installed)
- HPR commissioned and studies for performance identified
- New entry way and larger doors installed for easier installation of cryomodules for repair

Facility Plans

- **There is a Need for a Chemistry Facility**

- The facility will aid in the repair and maintenance activities addressing damaged cavities, and the reprocessing of cavities used in the linac
- This facility is necessary for the cleaning and processing of SRF structures for R&D to improve machine performance
- The facility is also necessary for process development for new cavities
 - **STS can benefit from this effort**


A Small Scale Chemistry Facility Concept Was Developed

The chemistry facility concept is designed as a low through put cavity and component processing facility

Plan submitted, reviewed and awaiting funding

Small Scale Chemistry Facility Concept

Cut View



Small Scale Chemistry Facility Capabilities:

- Electropolish Chemistry
 - Full cavities (low through put)
 - Small samples and cavity components

- Degreasing
 - Full cavities (moved from cleanroom)
 - Small samples and cavity components

HF free chemistry will be pursued to reduce risks and cost

Summary of SRF Activities

1. Large part of our effort is supporting linac operations
 - Developing and implementing repairs and improvements
 - Preparing for a spare MB cryomodule with cavity development
2. Supporting Plasma Processing R&D for future linac performance improvements
3. Developing, operating and maintaining SRF facilities to support above activities