

# Target Systems Performance and Plans



**T. McManamy**  
**NFDD Chief Engineer**


AAC Review Jan. 22-23,2008

# Outline

- **Performance history of Target Systems**
- **Beam Profile requirements in Operating Envelope**
- **Target System development to support power ramp up**
  - System development
  - New profile diagnostic development
  - Post Irradiation Examination planning
- **Rotating Solid Target development (LDRD)**

# Performance

Availability %



# Cooling Loops

- **All 4 loops have had nearly 100 % availability**
- **System performance consistent with design**
- **No water leaks on any loop or within core vessel**
- **One loop 2 pump failed**
  - **Automatic switch over to second pump accomplished**
  - **Failed pump replaced**

# Target Utilities – Performance

- **Equipment problems**
  - **PR2 magnetic drive cooling loop pump thrust bearing failure (likely due to pressure imbalance during startup)**
  - **Inflatable seal vacuum pump failure (actual operating pressure higher than recommended and pump overheated)**
  - **H2/O2 analyzers (original isolation amplifiers on H2 not working properly; grounding problems at Ring Injection Dump; restricted flow to analyzer, calibration issues)**
  - **Core vessel vacuum pump (controller electrical design problems)**

# Target and Mercury System


- **Shaft gas seal failure and grease leaks caused down time**
- **Repairs were performed in 2007 which have allowed stable operation**
  - **Sealed “tripod” zone with helium overpressure**
  - **Graphite packing added to grease seal**
  - **Pump speed reduced from 400 rpm to 150 rpm ( will allow up to 350 kW operation at this speed)**
  - **Higher pump speed and beam power are expected to be acceptable after graphite packing has been operated**
- **Target Protection System failures occurred because of lightning strikes**
  - **Surge protection added to system**

# Cryogenic Moderator System (CMS)

- **Helium Refrigeration System loss of capacity with time caused loss of availability**
- **Installing the helium heat exchanger in a vertical cold box has fixed the problem**
- **The 3 hydrogen loops have performed well**

# Mercury Offgas Treatment System (MOTS)

- Design flow 1.5 scfh helium (from Mercury Loop)
- Design pressure 16-17 psia



- **Design Changes:**

- Design flow and pressure required modification after mercury pump seal failed
  - pressure is now 13.6 psia, flow is still 1.5 scfh nominal but can be 6 scfh
- Considered a gold sorbent regeneration system, but do not believe that it is cost effective
- Designing a brine-chilled condenser system which should relieve the Hg load significantly thus greatly extending gold sorbent lifetime
- Parallel back-up carbon adsorber being designed
  - To be refrigerated instead of LN2 cooled



# **MOTS Problems Encountered (since April 2006)**

- **Dose rate issues with noble gas hold-up in the system**
  - Xenon conditioning of gold bed
  - Relocation/shielding of gold bed and CuO bed
  - CuO bed shielding not yet installed
  - Additional shielding to be considered when the need arises
- **Excess moisture issues**
  - Changed mol sieve bed design
    - regenerable beds instead of throw-away
  - Dried out system
    - Tritium was detected in the removed water
  - This issue is now resolved
- **Carbon Adsorber Reliability Issues**
  - Parallel back-up adsorber being designed

# Isotopes of Interest Detected in MOTS

|        |       |        |
|--------|-------|--------|
| Ar-41  |       |        |
| Kr-77  | Br-77 |        |
| Kr-79  |       |        |
| Kr-85m |       |        |
| Kr-87  |       |        |
| Kr-88  | Rb-88 |        |
| Xe-120 |       |        |
|        | I-121 | Te-121 |
| Xe-122 | I-122 |        |
| Xe-123 | I-123 |        |
| Xe-125 |       |        |
| Xe-127 |       |        |

- **All isotopes detected have >2 hr half lives**
- **There are other shorter lived isotopes that do not appear because their half lives are shorter and therefore decay in the Hg tank head space**
  - 2 hr holdup time
- **Xenon-127 (36 d) causes stack emissions when mercury loop is drained/filled**
  - Because gas flow is not through MOTS during system transients
  - Modification of piping and procedures may be required

# Other Systems- He, N2 and vacuum systems

- **Good overall availability**
  - Minor problems with core vessel helium system valve – corrected
  - Some instrumentation problems with hydrogen and oxygen monitoring systems for the gas liquid separator tanks
- **Core vessel has routinely maintained >99.95% helium**
  - Good seal performance and no significant leaks

# Beam Profile Requirements

- **Limits on the peak target beam intensity ( protons/ mm<sup>2</sup>/pulse) have been incorporated in the Operating Envelope**
- **The intent of the limits is to extend the target life while ramping up in power, particularly before a production capacity has been established for multiple targets per year**

# Target Lifetime Scaling

- The approach is based upon using an assumed life at 1 MW and 60 Hz with the nominal beam profile and scaling from that assumed life as shown below.
- $L/L_{1MW} = [1/E * I_0/I]^4 * (60/f) / C_f$

Where

L= target lifetime (beam-hours)

E= energy in GeV

I= Protons/mm<sup>2</sup>/pulse (  $I_0 = 1.3 \times 10^9$  )

f= frequency (Hz)

$C_f$ = ratio of damage per pulse at f versus at 60 Hz

# OE Intensity Limits below 400 kW

For  $L/L_{1MW}=F$

$$I=3.62 \times 10^{10} / E / [F * C_f * f]^{1/4}$$

**For F=13** ( 6 months if 1 MW life is 2 weeks)

f=30 hz, E=.88 Gev and  $C_f = 4$

$$I= 6.5 \times 10^9 \text{ Protons/mm}^2$$

f=60 hz, E=.88 Gev and  $C_f = 1$

$$I= 7.78 \times 10^9 \text{ Protons/mm}^2$$

# OE Intensity Limits below 400 kW con't

5.1.1.1.1 To have estimated target lifetimes of at least 6 months, the peak beam pulse intensity on Target is limited as given in the table below when operating at or below 400 kW.

- The peak Intensities may be exceeded by up to 10 % for 30 minutes.
- Peak Intensities > 25% of the limit require rapid beam shut down.

| Nominal rep rate (Hz) | Peak Protons/m <sup>2</sup> /pulse 880 MeV | Peak Protons/m <sup>2</sup> /pulse 1.0 GeV | Power at limit with nominal profile (kW) |
|-----------------------|--|--|--|
| 5                     | $8.1 \times 10^{15}$                       | $7.2 \times 10^{15}$                       | 46                                       |
| 15                    | $6.2 \times 10^{15}$                       | $5.4 \times 10^{15}$                       | 105                                      |
| 30                    | $6.5 \times 10^{15}$                       | $5.8 \times 10^{15}$                       | 221                                      |
| 60                    | $7.8 \times 10^{15}$                       | $6.8 \times 10^{15}$                       | 526                                      |

The normalized peaking factor allowed at 60 Hz and 400 kW is therefore 1.3 ( 526kW/400kW)

# Ramp-up from 400 kW to 1 MW

| Power (kW) | Normalized Peaking Factor | Peak Protons/m <sup>2</sup> /pulse @ 1 GeV, 60 Hz |
|------------|---------------------------|---|
| 400        | 1.3                       | <b>6.85 x 10<sup>15</sup></b>                     |
| 600        | 1.2                       | <b>9.49 x 10<sup>15</sup></b>                     |
| 800        | 1.1                       | <b>1.16 x 10<sup>16</sup></b>                     |
| 1000       | 1.0                       | <b>1.30 x 10<sup>16</sup></b>                     |

This assumes we can improve the peaking factors as we go up in power to match the ICD limit at 1 MW



# Actual Beam Peaking history

| Creation Date | Beam Energy (MeV) | Proton Per Pulse | Rep Rate (Hz) | Power    | Peak Proton Density Target | Normalized Peaking Factor Target | RMS Wdth Target (mm) | RMS Height Target (mm) |
|---------------|-------------------|------------------|---------------|----------|----------------------------|----------------------------------|----------------------|------------------------|
| 26-Dec-07     | 845               | 3.77E+13         | 30            | 1.53E+05 | 6.24E+09                   | 1.32                             | 37.4                 | 15.0                   |
| 18-Dec-07     | 845               | 3.94E+13         | 30            | 1.60E+05 | 5.86E+09                   | 1.19                             | 40.0                 | 14.9                   |
| 13-Dec-07     | 845               | 2.45E+13         | 60            | 1.99E+05 | 5.33E+09                   | 1.74                             | 32.3                 | 13.8                   |
| 4-Dec-07      | 845               | 4.16E+13         | 30            | 1.69E+05 | 6.51E+09                   | 1.25                             | 38.0                 | 16.4                   |
| 28-Nov-07     | 845               | 3.34E+13         | 30            | 1.36E+05 | 5.57E+09                   | 1.33                             | 35.1                 | 15.2                   |
| 15-Nov-07     | 845               | 2.58E+13         | 30            | 1.05E+05 | 4.38E+09                   | 1.36                             | 37.8                 | 16.1                   |
| 15-Nov-07     | 845               | 2.58E+13         | 30            | 1.05E+05 | 4.37E+09                   | 1.36                             | 37.8                 | 16.1                   |
| 30-Aug-07     | 885               | 3.25E+13         | 30            | 1.38E+05 | 6.08E+09                   | 1.50                             | 41.5                 | 14.6                   |
| 29-Aug-07     | 885               | 3.45E+13         | 30            | 1.47E+05 | 5.07E+09                   | 1.18                             | 41.5                 | 14.7                   |
| 23-Aug-07     | 885               | 2.81E+13         | 30            | 1.19E+05 | 4.36E+09                   | 1.24                             | 43.8                 | 15.5                   |
| 21-Aug-07     | 885               | 4.27E+13         | 30            | 1.82E+05 | 6.46E+09                   | 1.21                             | 46.7                 | 15.9                   |
| 16-Aug-07     | 885               | 3.65E+13         | 30            | 1.55E+05 | 4.63E+09                   | 1.02                             | 45.7                 | 16.0                   |
| 19-Jul-07     | 885               | 2.43E+13         | 30            | 1.03E+05 | 3.13E+09                   | 1.03                             | 48.0                 | 15.5                   |
| 21-Jun-07     | 885               | 1.50E+13         | 30            | 6.36E+04 | 2.13E+09                   | 1.14                             | 47.2                 | 14.3                   |
| 5-Apr-07      | 887               | 2.90E+13         | 15            | 6.18E+04 | 3.60E+09                   | 0.99                             | 52.0                 | 16.0                   |
| 28-Mar-07     | 887               | 2.70E+13         | 15            | 5.76E+04 | 3.90E+09                   | 1.16                             | 43.3                 | 15.5                   |
| 28-Mar-07     | 887               | 2.70E+13         | 15            | 5.76E+04 | 6.90E+09                   | 2.04                             | 40.2                 | 13.9                   |
| 28-Mar-07     | 887               | 4.20E+13         | 15            | 8.95E+04 | 5.56E+09                   | 1.06                             | 40.1                 | 15.7                   |
| 15-Mar-07     | 887               | 2.90E+13         | 15            | 6.18E+04 | 4.29E+09                   | 1.18                             | 44.2                 | 15.7                   |
| 6-Mar-07      | 887               | 2.41E+13         | 15            | 5.14E+04 | 4.21E+09                   | 1.40                             | 41.9                 | 14.8                   |

**Nominal Beam Profile has target peak ( p/mm<sup>2</sup>) = 1.3e-4\*# protons/pulse**

# Target System Development- Cooling loops

- Use of D<sub>2</sub>O in Reflector Plug loop (HWS/PR4) projected to improve neutron flux by ~15% for neutron energies ~ 1eV.
- HWS/PR4 Cooling Loop:
  - 2228 gallons circulating; 4823 gal total
    - ~5 MT (~1315 gallons) in 28 drums from Savannah River
      - “High purity” D2O: > 99.67 mol % D2O
      - Low levels of tritium ( $\leq 1.5$  mCi/L)
      - Weighed upon receipt and sampled for analysis
      - Does not meet SNS pH/pD, conductivity and impurity level requirements
      - Must be processed through temporary cleanup loop at SNS to remove impurities (tritium can not be removed)
    - ~15 MT (~3508 gallons) in ~67 drums from other source
  - PR4 Drying test planned for February-March 2008
- Controls Issues:
  - Inventory control
  - Flow meter re-calibration

# Target System Development- Hg

- **Target Module procurements started**
- **Spare Mercury Pump in fabrication/testing**


# Target System Development- Spares

- **Spare Inner Reflector Plug in design**
  - Incorporates improvements to reduce fabrication complexity while maintaining performance
  - Procurement package is being prepared now
- **Spare Proton Beam Window (PBW) on site**
  - Follow on procurement to start this year
- **Remote handling systems for PBW in fabrication**

# New Profile Diagnostic Development


- **Because of the importance of peak intensity on target life and the known uncertainties in current methods of estimating the peak, a new diagnostic is in development which will allow viewing the target nose region**
- **The design will allow viewing a temporary viewscreen to qualify new beam optics at reduced power by the beginning of next FY**
- **Future full power options will be studied next year including:**
  - **Viewing of a tungsten mesh**
  - **Viewing light from the helium**

# Viewscreen reflective optical path



Detail design of the optics is in progress

# Viewscreen – Fiber routing





Radiation Hard Fiber  
procurement started

Camera to be located outside  
of shutter drive equipment  
room



# Parabolic Al 6061 Mirror

- **Diamond Turned aluminum mirror in fabrication**
- **Threaded holes for mounting in PBW**
- **Provides ~ 200 mm diameter field of view at target nose**
- **Delivery in January**
- **Final optical design of turning mirror and focusing elements to fiber optical cable in progress**
- **Bench top testing of optical design planned**





# Post Irradiation Examination of Targets




**Final Saw  
Factory  
Acceptance  
Testing  
completed  
(March 07)**




# Post Irradiation Examination (PIE)

- The PIE Tooling is functionally ready – final mods for in-cell use are being completed.
- The vertical saw has been fully tested and is now being operated to optimize cutting speeds.
- The PIE Tooling will be installed after the first target change-out. This keeps the target service bay clear and allows the target activation to decay.
- Once installed, the PIE tooling will be left in cell until needed or replaced.



# PIE Samples


- **Target disassembly inside the cell will permit immediate visual observation of damaged areas.**
- **Tooling will reduce sections of interest to samples suitable for processing in Metallurgical Cells at ORNL.**





# PIE Secondary Tooling

- Numerous tools and containers have been built to support PIE operations:
  - Scrap Storage Container
  - Small Shear
  - Hole Drill
  - Hole Punch



# Rotating Solid Target Concept Development

- **Conceptual design for a solid rotating target for potential use in the second SNS target station has started as an LDRD project**
- **Design concepts are being developed for up to 3 MW operation with long pulses**
- **Neutronic evaluations are being done for such a target with two large coupled moderators above and below the target**
- **The LDRD is for 2 years and in the second year a mockup of the rotating seal and bearing system is to be tested**

# Preliminary Results

- Evaluations are being done at 3 MW and 20 hz for a tungsten/tantalum clad target 1 - 1.2 m in diameter and 70 - 80 mm thick
- Steady-state cooling does not appear to be a problem
- Moderator Neutronic performance is equal or better than for a mercury target
- Target lifetime for 10 dpa > 5 years
- Decay heat of ~35 kW probably requires a separate cooling loop in the hub region
- Bearings and seals can be located above the target and maintained separately
  - Much of the experience with the cantilever mercury pump is applicable to this design

# Summary

- **Target Systems are maturing and achieving excellent availability**
- **Planning is in progress for the next phase of operations as targets and other components reach the end of service life**
  - **Major component spares are being procured and are expected to be available prior to anticipated need dates**
  - **Handling systems for activated components are being procured ahead anticipated need dates**